CrossMark

ERRATUM

Erratum to: Developing a fatigue fracture model for asphalt overlay reinforced with geogrid

Shahab Fallah · Ali Khodaii

**Erratum to: Materials and Structures
DOI 10.1617/s11527-015-0606-6**

Due to an unfortunate turn of events the wrong version of Table 3 was published. Please find in this erratum the correct version of Table 3 that should be regarded as the final version by the reader.

Table 3 Aggregate grading

No	Sieve size (mm)	37.5	25	19	12.5	9	4.75	2.36	0.3	0.075
Aggregate grading for existing asphalt concrete										
1	Passing (%)	100	95	–	70	–	35	24	9	5
2			100	95	–	78	56	38	13	7
3				100	95	–	62	42	12	6
Aggregate grading for asphalt overlay										
1	Passing (%)			100	95	–	62	42	12	6
2					100	91	85	45	15	7
3					100	91	76	50	15	8

S. Fallah
Highway Division, Department of Civil and Environmental Engineering, Amirkabir University of Technology, Tehran, Iran
e-mail: shfallah@aut.ac.ir

A. Khodaii (✉)
Department of Civil and Environmental Engineering, Amirkabir University of Technology, Tehran, Iran
e-mail: khodaii@aut.ac.ir

rilem